

Running Contract Details	
Equipment Name	AIR CONDITIONER - VARIOUS TYPE
Running Contract Valid Till	28-03-2021
Tender Ref No	KMSCL/EP/T319/176/2019(R)
Tendered Quantity	1000
Supplier Name	M/s Maxsel Agencies
GST No	32AADFM0576G1ZL
Installation & Delivery Period	8 Week(s)
Up-time / PM vist	95% & 4 Visits per year
Warranty period	1 Years

Supplier`s Details		
Address	Contact Details	
St. Thomas Shopping Complex. Near Jawahar Balabhavan Kadappakadu Kollam-691001	Contact Person	Gopalakrishnan Pillai
	Phone	0474-2745755
	Mobile No	9847070004
	Email	maxselagencies@gmail.com

Item-wise Price Details				
#	Item Details	Unit Rate (Incl.all taxes & charges)	Service Charges (Through KMSCL)	Grand Total
1	<b>Air conditioner 2 Ton</b> <i>Model &amp; Make : 24 ENXA / LG Inverter Type</i>	58990 Incl.GST :28%	3806.7	62796.7
2	<b>Air conditioner 1.5 Ton</b> <i>Model &amp; Make : 18 ENXA / LG Inverter Type</i>	47360 Incl.GST :28%	3056.2	50416.2
3	<b>Air conditioner 1 Ton</b> <i>Model &amp; Make : 12 ENXA / LG Inverter Type</i>	40709.99 Incl.GST :28%	2627.07	43337.06
		<b>147059.99</b>	<b>9489.97</b>	<b>156549.96</b>

Annual / Comprehensive Maintenance Charges (Exl.Tax)				
Rate	2 <sup>ND</sup> Year	3 <sup>rd</sup> Year	4 <sup>th</sup> Year	5 <sup>th</sup> Year
<b>Air conditioner 2 Ton</b>				
Labour	1,200.00	1,400.00	1,600.00	1,800.00
Comprehensive	2,200.00	3,000.00	3,500.00	4,000.00

<b>Annual / Comprehensive Maintenance Charges (Exl.Tax)</b>				
<b>Air conditioner 1.5 Ton</b>				
<b>Labour</b>	1,000.00	1,200.00	1,400.00	1,600.00
<b>Comprehensive</b>	2,000.00	2,500.00	3,000.00	3,500.00
<b>ve</b>				
<b>Air conditioner 1 Ton</b>				
<b>Labour</b>	1,000.00	1,200.00	1,400.00	1,600.00
<b>Comprehensive</b>	2,000.00	2,500.00	3,000.00	3,500.00
<b>ve</b>				

### **Other terms & conditions**

1. The supplier shall execute an agreement with the purchaser as per tender conditions (agreement format is given in the tender document).
2. The supplier shall submit performance security amounting to 5% of the value of the supply order.
3. The labour & comprehensive charges of equipment after the completion of warranty period is finalized by KMSCL as mentioned above.
4. Since discount rate is not applicable for equipment under Running Contract of KMSCL, purchase/supply order can be issued directly to supplier at the given rate with tax & other charges (exclusive of KMSCL service charges).
5. If purchase/supply order is issued directly to the supplier, KMSCL service charge need not be paid. But the copy of the said order may be forwarded to KMSCL for information.

### **Technical Specification**

#### **Equipment :Air conditioner 2 Ton**

1. Star rating : 3 Star
2. Cooling Capacity(KW/hr): above 6000KW/hr
3. Material of condenser coil: Copper
4. Compressor Type: Rotary type/ Scroll type
5. Compressor warranty: 5 years
6. Air circulation(CFM H/M/L): above 500/450/350
7. Moisture Removal(L/hr): above 1.8
8. IDU Noise level(dBA) : ? 55/50/45
9. Control : Microprocessor controlled codeless remote
10. Power Source (V/Hz/Ø) : 230V /50Hz / single phase
11. Display : LED/LCD

12. Remote control distance : Min 10 meters

## II. Voltage Stabilizer

1. Voltage Stabilizer Wall mount type with Time delay, High & low voltage & Thermal overload protection.
2. Capacity: 5 KVA
3. Warranty: 2 years
4. Input voltage: 170-220 V
5. Output Voltage : 200-240 V
6. High Voltage Cut Off : 240
7. Efficiency: >95%
8. Frequency : 50Hz

## III. Items to be supplied along with :

1. 3 mtr copper piping with superlon insulation for suction line
2. 3 mtr copper piping with superlon insulation for Discharge line
3. 1 mtr PVC piping for drain
4. Indoor – Outdoor unit connecting power cable and required cable from power socket to stabilizer and from stabilizer to AC Unit
5. Base plate for hanging indoor unit
6. Suitable 3pin plug top shall be provided

### **Equipment : Air conditioner 1.5 Ton**

1. Star rating : 3 Star
2. Cooling Capacity(KW/hr): above 4500KW/hr
3. Material of condenser coil: Copper
4. Compressor Type: Rotary type
5. Compressor warranty: 5 years
6. Air circulation(CFM H/M/L): above 450/350/300
7. Moisture Removal(L/hr): above 1.5
8. IDU Noise level(dBA) : ? 55/50/45

9. Control : Microprocessor controlled codeless remote
10. Power Source (V/Hz/Ø) : 230V /50Hz / single phase
11. Display : LED/LCD
12. Remote control distance : Min 10 meters

## II. Voltage Stabilizer

1. Voltage Stabilizer Wall mount type with Time delay,High& low voltage& Thermal overload protection.
2. Capacity: 4 KVA
3. Warranty: 2 years
4. Input voltage: 170-220 V
5. Output Voltage : 200-240 V
6. High Voltage Cut Off : 240
7. Efficiency: >95%
8. Frequency : 50Hz

## III. Items to be supplied along with :

1. 3 mtr copper piping with superlon insulation for suction line
2. 3 mtr copper piping with superlon insulation for Discharge line
3. 1 mtr PVC piping for drain
4. Indoor – Outdoor unit connecting power cable and required cable from power socket to stabilizer and from stabilizer to AC Unit
5. Base plate for hanging indoor unit
6. Suitable 3pin plug top shall be provided

### **Equipment :Air conditioner 1 Ton**

1. Star rating : 3 Star
2. Cooling Capacity(KW/hr): above 3000KW/hr
3. Material of condenser coil: Copper
4. Compressor Type: Rotary type
5. Compressor warranty: 5 years

6. Air circulation(CFM H/M/L): above 300/250/200
7. Moisture Removal(L/hr): above 1
8. IDU Noise level(dBA) : ? 45/40/35
9. Control : Microprocessor controlled codeless remote
10. Power Source (V/Hz/Ø) : 230V /50Hz / single phase
11. Display : LED/LCD
12. Remote control distance : Min 10 meters

## II. Voltage Stabilizer

1. Voltage Stabilizer Wall mount type with Time delay,High& low voltage& Thermal overload protection.
2. Capacity: 4 KVA
3. Warranty: 2 years
4. Input voltage: 170-220 V
5. Output Voltage : 200-240 V
6. High Voltage Cut Off : 240
7. Efficiency: >95%
8. Frequency : 50Hz

Miscellaneous Details					
#	Name of the Item	Basic Price(Rs)	GST(Rs)	Cust.Tax(Rs)	Misc.Charges(Rs)
1	Copper Pipe with Superlon Insulation for Suction and Discharge and Indoor - Outdoor Connecting Cable per running metre	932.20	167.78	0.00	0.00
2	Drain Pipe (PVC) per running metre.	93.22	16.76	0.00	0.00
3	Concealing	1016.94	183.04	0.00	0.00
4	Supporting Stand for Outdoor Unit	847.45	152.54	0.00	0.00
5	Core cutting charge	1016.94	183.04	0.00	0.00
6	Dismantling old Split AC unit	847.45	152.54	0.00	0.00